

REPORT



3933 US ROUTE 11 CORTLAND, NEW YORK 13045

Order No. 3127463

Date: July 27, 2007

REPORT NO. 3127463CRT-001g

IMPACT SOUND TRANSMISSION TEST AND
CLASSIFICATION OF ENGINEERED HARDWOOD
FLOORING OVER SOUND SHARK 12MM UNDERLAYMENT
OVER A WOODJOIST FLOOR/CEILING ASSEMBLY
WITH A 1½INCH THICK LIGHTWEIGHT CONCRETE TOPPING

RENDERED TO:

SOUND SEAL 50 H. P. ALMGREN DRIVE AGAWAM, MA 01001

INTRODUCTION

This report gives the results of an Impact Sound Transmission test and the determination of the Impact Insulation Class of Engineered Hardwood Flooring over Sound Shark 12mm Underlayment. The underlayment was selected and supplied by the client and received at the laboratories on July 2, 2007. The underlayment appeared to be in a new, unused condition.

AUTHORIZATION

Signed Intertek Quotation No. 500038104.

TEST METHOD

The floor system was tested in general accordance with the American Society for Testing and Materials designation ASTM E492-04, "Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine". It was classified in accordance with ASTM E989-89 (Re-approved 1999), entitled, "Standard Classification for Determination of Impact Insulation Class (IIC)".

An independent organization testing for safety, performance, and certification.

Date: July 27, 2007

GENERAL

The test method is designed to measure the impact sound transmission performance of a floor-ceiling assembly, in a controlled laboratory environment. A standard tapping machine (Bruel & Kjaer Type 3207) was placed at four positions on a test floor that forms the horizontal separation between two rooms, one directly above the other. The data obtained was normalized to a reference room absorption of 10 square meters in accordance with the test method.

The standard also prescribes a single-figure classification rating called "Impact Insulation Class, IIC" which can be used by architects, builders and code authorities for acoustical design purposes in building construction.

The IIC is obtained by matching a standard reference contour to the plotted normalized one-third octave band sound pressure levels at each test frequency. The greater the IIC rating, the lower the impact sound transmission through the floor-ceiling assembly.

DESCRIPTION OF THE FLOOR/CEILING ASSEMBLY

The test floor is a 100 sq. ft. opening that forms the horizontal separation of the two rooms, one directly above the other. The structural members are open webbed wood floor trusses, 16 inches deep installed 24 inches on center. The sub flooring is 5/8 inch thick tongue and groove plywood. The bridging is a continuous 2×4 nailed to the bottom chord and the sides of the diagonals with 2 inch long nails. Single leaf RC-1 resilient channels $(2\frac{1}{2})$ inch $(2\frac{1}{2})$ inch $(2\frac{1}{2})$ inches on center and attached to the bottom chord by screws. The insulation is $(2\frac{1}{2})$ inches cellulose with a density of $(2\frac{1}{2})$ inches thick, with the long edges located between the joists perpendicular to the resilient channels. Short edges are staggered by $(2\frac{1}{2})$ inches are fastened to the resilient channels by means of $(2\frac{1}{2})$ inches on center. Joints are taped and $(2\frac{1}{2})$ inches from the long edges; screws are spaced $(2\frac{1}{2})$ inches on center. Joints are taped and finished with two layers of compound.

The topping over the tongue and groove plywood sub-floor is 1½ inches of lightweight concrete.

DESCRIPTION OF TEST SPECIMEN

The test specimen consisted of 3/8 inch thick Engineered Hardwood Flooring over Sound Shark 12mm thick recycled rubber underlayment laid on the concrete floor.

RESULTS OF TEST

The data obtained in the room below the panel normalized to A_o = 10 square meters, is as follows:

| 1/3 Octave Band | |
|-------------------------------|--------------------------------|
| Center Frequency | 1/3 Octave Band Sound Pressure |
| <u>Hertz</u> | Level dB re 0.0002 Microbar |
| | |
| 100 | 63 |
| 125 | 58 |
| 160 | 58 |
| 200 | 60 |
| 250 | 57 |
| 315 | 52 |
| 400 | 52 |
| 500 | 49 |
| 630 | 44 |
| 800 | 38 |
| 1000 | 29 |
| 1250 | 24 |
| 1600 | 22 |
| 2000 | 23 |
| 2500 | 24 |
| 3150 | 22 |
| | |
| Impact Insulation Class (IIC) | 57 |

PRECISION


The 95% uncertainty level for each tapping machine location is less than 3 dB for the 1/3 octave bands centered in the range from 100 to 400 Hz and less than 2.5 dB for the bands centered in the range from 500 to 3150 Hz.

For the floor/ceiling construction, the 95% uncertainty limits (ΔL_n) for the normalized sound pressure levels were determined to be less than 2 dB for the 1/3 octave bands centered in the range from 100 to 3150 Hz.

Date: July 27, 2007

ENGINEERED HARDWOOD FLOORING OVER SOUND SHARK 12MM UNDERLAYMENT INSTALLED OVER A WOOD JOIST FLOOR/CEILING ASSEMBLY WITH A 1½ INCH THICK LIGHTWEIGHT CONCRETE TOPPING

Impact Insulation Class



SOUND SEAL

REMARKS

1. Curing Period: None

2. Ambient Temperature: 75°F

3. Relative Humidity: 47%

CONCLUSION

The test method employed for this test has no pass-fail criteria; therefore, the evaluation of the test results is left to the discretion of the client.

Date of Test: July 26, 2007

Report Approved by:

For Patrick J. Schoof

Engineering Team Leader

Acoustical Testing

Report Reviewed By:

James R. Kline

Engineer/Quality Supervisor

Acoustical Testing

Attachments: None